

T/01
Schedule of Tender
P.W.D.Nagar Nigam Allahabad

Estimated Cost Rs 6, 10,000/--

Tender due on: 08-07-2011

Earnest money Rs: 61,000/--

Tender cost Rs 500/-

Name of work: अलापुर बाघम्बरी हाउसिंग स्कीम में तुलसी पार्क के डडिया नाले तक नाली एवं पुलिया तथा ई0डब्लू0एस0 ब्लॉक संख्या-1 से 6 तक गली का निर्माण।

Name of Contractor

J.E.

A.E.

S.No:	Quantity	Particulars	Rate/per
1	189.00cum	Earth work in excavation in ordinary soil upto 1.5 M lift & 30 M lead (S.I. No. 251)	60.00/Cum
2	123.00cum	Earth work in cutting/embank-cement in ordinary soil filling to be done in 20cm layer excavation to in the form on regular pits not exceeding 0.50 Mt including 30Mt lead & 1.5 M lift with all labour T&P (S.I. No. 253)	42.00/Cum
3	64.00cum	Concrete with 4 cm gauge brick ballast white lime & surkhi in 100:16:32 including all complete (S.I. No. 272)	1600.00/Cum
4	92.00cum	M-150 brick work in 1:6 ratio with cement and sand mortar in foundation with all labour T&P complete work.	2100.00/Cum
5	474.40sqm	Struck cement pointing in 1:2 cement and sand mortar with all labour T&P complete.	66.00/Sqm
6	156.00sqm	Flush cement pointing in 1:2 cement and sand mortar with all labour T&P complete.	50.00/Sqm
7	350.00cum	Providing & laying 60MM thick cement interlocking including 5 cm thick sand in based with all complete	524.00/Cum
8	1.00 job	Dismantling old of old power road with all complete	1000.00 job
9	40.00qtl	Providing Baralaty with bars ballast rofe etc. with all complete.	100.00 qtl.
10	17.00cum	Dismantling of brick with cement mortar (S.I. No. 692)	92.00/Cum
11	294.00cum	Cartage/disposal of earth upto 3 Km. Distance form site including loading unloading etc.	93.00/Cum
12	8.10sqm	R.C.C. work in slab in 1:2:4 with cement, coarse sand & 20mm appd stone grit with lab mat T&P including its centering & shuttering (S.I. No. 284)	4550.00/sqm
13	6.40sqm	M.S. or iron work in R.C.C. slab including bending binding etc. (S.I. No. 504)	4250.00/sqm
14	5000 Nos 6.50 Cum	Deduction cost of old material found at site A- Brick B- Brick bats	3500/% 350/Cum

I/We are registered as.....class contractor for the authorized to road/building/sewer/electrical work/water mains and supply of materials for the current year and are authorized to tender for this work as per regd.

I/We have deposited earnest money as detailed given below:

N.S.C.C.D.R.F.D.R No:

Dated

O I/We hereby agreed to execute the above work at in fig..... % (percentage) above/below the above estimate rate based on prevalent schedule of rate.

Contractor

T/02
Schedule of Tender
P.W.D.Nagar Nigam Allahabad

Estimated Cost Rs 69, 184/--

Tender due on: 08-07-2011

Earnest money Rs: 7,000/--

Tender cost Rs 50/-

Name of work: रसूलाबाद में ई0डब्लू0एस0 कालोनी में ब्लाक नं0 9 श्री जगदीश तिपाठी के मकान के पास गहरी नाली का निर्माण।

Name of Contractor

J.E.

A.E.

S.No:	Quantity	Particulars	Rate/per
1	50.00cum	Earth work in excavation in ordinary soil upto 1.5 M lift & 30 M lead (S.I. No. 251)	60.00/Cum
2	8.00cum	Laying C.C. in 12:6:1 with 40M gauge B.B. fine sand and cement including all labour material T&P.	1600.00/Cum
3	21.30cum	M-150 brick work in 1:6 ratio with cement and fine sand mortar in foundation plinth including all complete.	2100.00/Cum
4	80.00sqm	Struck cement pointing in 1:2 with cement and sand mortar including with all complete.	66.00/Sqm
5	28.00sqm	Flush cement pointing in 1:2 cement and sand mortar with all labour T&P complete.	48.00/Sqm
6	35.00cum	Cartage/disposal of earth upto 3 Km. Distance form site including loading unloading etc.	93.00/Cum

I/We are registered as.....class contractor for the authorized to road/building/sewer/electrical work/water mains and supply of materials for the current year and are authorized to tender for this work as per regd.

I/We have deposited earnest money as detailed given below:

N.S.C.C.D.R.F.D.R No:

Dated

O I/We hereby agreed to execute the above work at in fig..... %(percentage) above/below the above estimate rate based on prevalent schedule of rate.

Contractor

T/03
schedule of Tender
P.W.D.Nagar Nigam Allahabad

Estimated Cost Rs 2,20,200/--

Tender due on : 08-07-2011

Earnest money Rs: 22,200/--

Tender cost Rs 150/-

Name of work: कालिन्दीपुरम् में श्री पवन जायसवाल के मकान के सामने रोड पटरी तथा गली का सुधार।

Name of Contractor

J.E.	A.E.		
S.No:	Quantity	Particulars	Rate/per
1	179.00sqm	Dismantling of C.C. Flss including all comp.	11.00/Sqm
2	77.79cum	Earth work in cutting in ordinary soil including all complete the work.	42.00/Cum
3	18.00cum	Base concrete in 1:6:12 cement sand brick ballast including all complete.	1600.00/Cum
4	28.30 cum	M-150 class brick work in with 1:6 c/s mortor including all completes the work.	2100.00/Cum
5	56.24sqm	Struck cemetrn pointing in 1:2 motror and fine sand m&t including all complete.	66.00/Sqm
6	15.49cum	R.C.C. work in slob in 1:2:4 with cement sand & 20mm. Savge stone grit including all complete.	4550.00/Cum
7	4.30 qtl	Mild steel in R.C.C. slob including all complete.	4250.00 Qtl
8	179.00Sqm	Supply and laying of 80M thick Cement & work interlocking including 4cm thick sand base etc. all complete.	644.00/Sqm
9	50.00cum	Cartage/Disposal of earth upto 3 Km. Including all complete.	83.40/Cum

I/We are registered as.....class contractor for the authorized to road/building/sewer/electrical work/water mains and supply of materials for the current year and are authorized to tender for this work as per regd.

I/We have deposited earnest money as detailed given below:

N.S.C.C.D.R.F.D.R No:

Dated

O I/We hereby agreed to execute the above work at in fig.....%(percentage) above/below the above estimate rate based on prevalent schedule of rate.

Contractor

T/04
Schedule of Tender
P.W.D.Nagar Nigam Allahabad

Estimated Cost Rs 91,900/--

Tender due on : 08-07-2011

Earnest money Rs: 9,200/--

Tender cost Rs 50/-

Name of work मालविय नगर में 41,42,45, 35, 61 ,56/45, 30 तक गली का सुधार।

Name of Contractor

S.No:	Quantity	Particulars	Rate/per
1	30.15cum	Earth work in excavation in ordinary soil upto 1.5 Mt. 30 lead at all complete.	48.00/Cum
2	12.06cum	Base Concrete 1:6:12 cement mortar at the site with all complete work.	1600.00/Cum
3	5.80cum	M-150 brick work in 1:6 ratio with cement and sand mortar in foundation with all labour T&P complete work.	2100.00/Cum
4	24.40sqm	Struck cement pointing in 1:2 cement and sand mortar with all labour T&P complete.	66.00/Sqm
5	102.00sqm	Providing New F.S. 1:6 Cement sand mortar at the site with all complete work.	285.00/Sqm
6	69.60sqm	Providing New F.S. 1:6 Cement sand mortar at the site with all complete work.	126.00/Sqm
7	2.85cum	Providing C.C. 1:2:4 cement sand mortar at the site with all complete work.	3600.00/Cum
8	2.00 job	Providing Baralaty with bars ballast rofe etc. with all complete.	991.00 qtl.
9	0.72sqm	R.C.C. 1:2:4 cement, sand mortar at the site with all complete work.	4550.00/sqm
10	0.56 qtl	Mild steel in R.C.C. slob including all complete work.	4250.00 Qtl
11	30.15cum	Cartage/disposal of earth upto 3 Km. Distance form site including loading unloading etc.	83.45/sqm
12	200 Nos 4.00 Cum	Deduction cost of old material found at site A- Brick B- Brick bats	3500/% 350/Cum

I/We are registered as.....class contractor for the authorized to road/building/sewer/electrical work/water mains and supply of materials for the current year and are authorized to tender for this work as per regd.

I/We have deposited earnest money as detailed given below:

N.S.C.C.D.R.F.D.R No:

Dated

O I/We hereby agreed to execute the above work at in fig..... % (percentage) above/below the above estimate rate based on prevalent schedule of rate.

Contractor

T/05
Schedule of Tender
P.W.D.Nagar Nigam Allahabad

Estimated Cost Rs 1,09,120/--

Tender due on : 08-07-2011

Earnest money Rs: 11,000/--

Tender cost Rs 100/-

Name of work: नेहरू नगर मीरापुर में म0नं0 30/29, 30/28, 26 के पास गली नाली पटरी का सुधार।

Name of Contractor

J.E.	A.E.		
S.No:	Quantity	Particulars	Rate/per
1	87.00cum	Earth work in excavation ordinary soil including all complete.	48.00/Cum
2	10.50cum	Dismantling of B/W including all complete work.	98.00/Cum
3	3.00 Job	Cleaning of Silt from drain including all complete	1000.00 Job
4	7.70cum	Base cement concrite 1:6:12 including all complete.	1600.00/Cum
5	23.50Cum	M-150 brick work in 1:4 cement and sand mortor in foundation with all labour T&P complete work.	2100.00 /Cum
6	100.00sqm	Struck cement pointing 1:2 cement & sand mortor including all complete.	66.00/Sqm
7	37.50sqm	New F.S. 1:6 cement & sand mortor including all complete.	285.00/sqm
8	120.00sqm	Relaying B.O.E. dry joint filled local sand all complete.	32.50/sqm
9	120.00sqm	New B.O.E. dry including all complete.	195.00/sqm
10	87.00sqm	Cartage of earth upto 3 Km. Distance form site including loading unloading etc.	83.40/sqm
11	3000 Nos 6.00 Cum	Deduction cost of old material found at site A- Brick B- Brick bats	3500/% 350/Cum

I/We are registered as.....class contractor for the authorized to road/building/sewer/electrical work/water mains and supply of materials for the current year and are authorized to tender for this work as per regd.

I/We have deposited earnest money as detailed given below:

N.S.C.C.D.R.F.D.R No:

Dated

O I/We hereby agreed to execute the above work at in fig.....%(percentage) above/below the above estimate rate based on prevalent schedule of rate.

Contractor

T/06
Schedule of Tender
P.W.D.Nagar Nigam Allahabad

Estimated Cost Rs 1,78,000/--

Tender due on : 08-07-2011

Earnest money Rs: 18,000/--

Tender cost Rs 100/-

Name of work अतरसुर्य्या में श्री राम लाल किशोरी लाल एवं लाजपत स्कूल वाली गली में दूषित जल निकासी हेतु नाला एवं पुलिया निर्माण।

Name of Contractor

J.E.

A.E.

S.No:	Quantity	Particulars	Rate/per
1	7.20cum	Dismantling of old brick work with cement mortor including all complete the work.	92.00/Cum
2	11.00sqm	Scrapping of road surface including all complete the work.	8.00/Sqm
3	33.00cum	Earth work as in excavation in found in ordinary soil 1.50mt lift & 30.0mt. lead including all complete the work .	48.00/Cum
4	17.00Cum	P.C.C. 1:6:12 with cement fine sand & 40mm gavage brick ballast including all complete the work.	1600.00/Cum
5	10.50Cum	M-150 brick work in found with 1:6 cement and sand mortor all complete the work.	2100.00 /Cum
6	142.00sqm	Struck cement pointing in 1:2 cement and sand mortor with all labour T&P complete.	66.00/Sqm
7	10.00sqm	Flush cement pointing in 1:2 cement and sand mortor with all labour T&P complete.	50.00/Sqm
8	6.00cum	R.C.C. work in slob in 1:2:4 with cement sand & 20mm. gritt.	4550.00/Cum
9	4.72Qtl	Mild steel (Tar or Plain) for R.C.C. slab including cutting bending wastage etc all complete the work.	4250.00/Qtl
10	8.00cum	P/L 1:2:4 with cement course cord & 20mm. Savge stone grit including on completes the work.	3600.00/Cum
11	3.00Qtl	M.S. or iron work for heavy work.	4700.00/Qtl
12	13.50sqm	P/L of new F.S. with 1:6 C/S mortor.	285.00/Sqm
13	18.00sqm	Relaying of F.S. with 1:6 C/S mortor.	126.00/Sqm
14	1700.00Nos	Deduction of old brick.	3500.00 Nos
15	8.50Cum	Deduction of old brick ballast.	350.00/Cum

I/We are registered as.....class contractor for the authorized to road/building/sewer/electrical work/water mains and supply of materials for the current year and are authorized to tender for this work as per regd.

I/We have deposited earnest money as detailed given below:

N.S.C.C.D.R.F.D.R No:

Dated

O I/We hereby agreed to execute the above work at in fig.....%(percentage) above/below the above estimate rate based on prevalent schedule of rate.

Contractor

T/07
Schedule of Tender
P.W.D.Nagar Nigam Allahabad

Estimated Cost Rs. 8,06,625/--

Tender due on : 08-07-2011

Earnest money Rs: 81,000/--

Tender cost Rs 500/-

Name of work : मालविय नगर में अहिराना रोड के शेष कार्य का निर्माण।

Name of Contractor

J.E.	A.E.		
S.No:	Quantity	Particulars	Rate/per
1	759.01sqm	Dismantling of existing old damaged of c.c. flag stone. including s/o usable brick found at site use in work.	70.00Sqm
2	1.43cum	Dismantling of brick work at the site.	88.00/Cum
3	152.37cum	Earth work as in excavation in found in ordinary soil 1.50mt lift & 30.0mt. Lead including all completes the work.	48.00/Cum
4	60.80Cum	B.E.E. 1:6:12 with cement fine sand & 40mm gavage brick ballast including all complete the work.	1600.00/Cum
5	43.71Cum	M-150 brick work in found with 1:6 cement and sand mortar all complete the work.	2100.00 /Cum
6	80.50sqm	Struck cement pointing in 1:2 cement and sand mortar with all labour T&P complete.	66.00/Sqm
7	42.00sqm	Flush cement pointing in 1:2 cement and sand mortar with all labour T&P complete.	42.00/Sqm
8	2.00 Job	Providing ballast etc all complete work.	991.00 Job
9	4.25cum	R.C.C. work in slob in 1:2:4 with cement sand & 20mm. gritt.	4550.00/Cum
10	3.33Qtl	Mild steel (Tar or Plain) for R.C.C. slab including cutting bending wastage etc all complete the work.	4250.00/Qtl
11	1.92cum	C.C. 1:2:4 with cement course cord & 20mm. Savg stone grit including on completes the work.	3600.00/Cum
12	760.00sqm	S/F of 80 mm thick interlocking work with all complete work.	644.00/Sqm
13	153.52cum	Cleaning of earth upto 3 Km distance from site takes in all work.	83.40cum
14	22.50sqm	Cleaning F.S. & cement 1:6 and mortar including all complete work.	285.00sqm
15	250 Nos 1.00 Cum	Deduction cost of old material found at site A- Brick B- Brick bats	3500/% 300/Cum

I/We are registered as.....class contractor for the authorized to road/building/sewer/electrical work/water mains and supply of materials for the current year and are authorized to tender for this work as per regd.

I/We have deposited earnest money as detailed given below:

N.S.C.C.D.R.F.D.R No:

Dated

O I/We hereby agreed to execute the above work at in fig.....%(percentage) above/below the above estimate rate based on prevalent schedule of rate.

Contractor

T/08

Schedule of Tender

P.W.D.Nagar Nigam Allahabad

Estimated Cost Rs 70,000/--

Tender due on : 30-6-2011

Earnest money Rs: 7,000/--

Tender cost Rs 50/-

Name of work कमला नगर में अनुसूचित जाति के महिला के घर के निकट गहरी नाली निर्माण।

Name of Contractor

J.E.

A.E.

S.No:	Quantity	Particulars	Rate/per
1	40.0cum	Earth work as in excavation in found in ordinary soil 1.50mt lift & 30.0mt. Lead including all completes the work.	48.00/Cum
2	7.13Cum	B.C.C. 1:6:12 with cement fine sand & 40mm gavage brick ballast including all complete the work.	1600.00/Cum
3	21.65cum	M-150 its class brick work in 1:6 cement and sand mortar in foundation with all labour T&P complete work.	2100.00 sqm
4	89.91sqm	Struck cement pointing in 1:2 with cement and fine sand mortar including all complete (S.I. No. : 574)	66.00sqm
5	36.45sqm	Flush cement pointing in 1:2 cement and sand mortar with all labour T&P complete.	50.00/Sqm
6	40.09cum	Disposal of lurplus earth upto 3Km distance with all loading unloading labour T&P.	83.40/Cum

I/We are registered as.....class contractor for the authorized to road/building/sewer/electrical work/water mains and supply of materials for the current year and are authorized to tender for this work as per regd.

I/We have deposited earnest money as detailed given below:

N.S.C.C.D.R.F.D.R No:

Dated

O I/We hereby agreed to execute the above work at in fig..... %(percentage) above/below the above estimate rate based on prevalent schedule of rate.

Contractor

T/09
Schedule of Tender
P.W.D.Nagar Nigam Allahabad

Estimated Cost Rs 2,27,200/--

Tender due on : 08-07-2011

Earnest money Rs: 23,000/--

Tender cost Rs 150/-

Name of work: नैनी में वार्ड 36 इन्दलपुर रोड ओवर ब्रीज के नीचे एग्रीकल्चर गेट के पास नाला तथा मार्ग का सुधार।

Name of Contractor

J.E.

A.E.

S.No:	Quantity	Particulars	Rate/per
1	85.00cum	Earth work as in excavation in found in ordinary soil 1.50mt lift & 30.0mt. Lead including all completes the work.	48.00/Cum
2	10.00Cum	P/L P.C.C. with 1:6:12 cement fine sand & 40mm gavage brick ballast including all complete the work.	1600.00/Cum
3	41.03cum	M-150 its class brick work in 1:4 cement and sand mortor in foundation with all labour T&P complete work.	2200.00m
4	166.00sqm	Struck cement pointing in 1:2 with cement and fine sand mortor including all complete (S.I. No. : 574)	66.00sqm
5	42.00sqm	Flush cement pointing in 1:2 cement and sand mortor with all labour T&P complete.	48.00/Sqm
6	3.40cum	R.C.C. work in slob in 1:2:4 with cement sand & 20mm. gritt.	4550.00/Cum
7	4.00Qtl	Mild steel (Tar or Plain) for R.C.C. slab including cutting bending wastage etc all complete the work.	4250.00/Qtl
8	20.00cum	Supply of 25, 50 mm savage sand brick stone ballast all compe.	642.00/Cum
9	4.00cum	Supply of mortor.	416.00/Cum
10	20.00cum	Consolidation of above 40-63 mm size with road roller labour water T&P etc. complete.s	115.00/Cum
11	20.00cum	water allowed be all complete.	26.00/Cum
12	15.00cum	P/L C.C with 1:2:4 cement sand & 20mm sand stone ballast all complete.	3600.00/Cum

I/We are registered as.....class contractor for the authorized to road/building/sewer/electrical work/water mains and supply of materials for the current year and are authorized to tender for this work as per regd.

I/We have deposited earnest money as detailed given below:

N.S.C.C.D.R.F.D.R No:

Dated

O I/We hereby agreed to execute the above work at in fig.....%(percentage) above/below the above estimate rate based on prevalent schedule of rate.

Contractor

T/10
Schedule of Tender
P.W.D.Nagar Nigam Allahabad

Estimated Cost Rs. 1,88,904/--

Tender due on : 08-07-2011

Earnest money Rs: 19,000/--

Tender cost Rs 100/-

Name of work :- अल्लापुर संजय नगर मलिन बस्ती में रेलवे डट पुल से बक्सी बाँध के पास तक नाली निर्माण।

Name of Contractor

J.E.

A.E.

S.No:	Quantity	Particulars	Rate/per
1	101.00cum	Earth work in Excavation in ordinary soil upto 1-5 M lift & 30 M lead (S.I. No. 251)	48.00/Cum
2	14.00 cum	Laying C.C. in 12:6:1 with 40m gauge B.B. fine sand and cement including all labour material T&P (S.I. No. 772)	1600.00/Cum
3	56.67 cum	Same as above I.No: 6 but in 1:4 ratio (S.I. No. 305)	2200.00/Cum
4	255.60cum	Struck cement pointing in 1:2 with cement and fine mortar including all complete.	66.00/Cum
5	72.00Sqm	Flush pointing in 1:2 with cement and fine sand mortar with all labour material T&P.	50.00/Sqm
6	91.00cum	Cartage/disposal of earth upto 3Km distance from site including loading unloading etc.	83.40/Cum
7	0.80Qtl	M.S. of iron work in R.C.C. slab including bending blending etc.	4250.00/Cum

I/We are registered as.....class contractor for the authorized to road/building/sewer/electrical work/water mains and supply of materials for the current year and are authorized to tender for this work as per regd.

I/We have deposited earnest money as detailed given below:

N.S.C.C.D.R.F.D.R No:

Dated

O I/We hereby agreed to execute the above work at in fig..... %(percentage) above/below the above estimate rate based on prevalent schedule of rate.

Contractor