

T/1
Schedule of Tender
P.W.D.Nagar Nigam Allahabad

Estimated Cost Rs. 9,96,710/--

Tender due on: 07-09-2011

Earnest money Rs: 99,671/--

Tender cost Rs 500/-

Name of work : वार्ड- 12 मलाकराज में रेलवे लाईन के किनारे नाला निर्माण तथा आर0सी0सी0 कवर कार्य भाग-3।

Name of Contractor

J.E.

A.E.

S.No:	Quantity	Particulars	Rate/per
1	28.00cum	Dismantling of Brick Work with all complete the work.	92.00/Cum
2	85.00cum	M-150 brick work in 1:6 with cement and fine sand mortor with all ocomplete.	2100.00 /Cum
3	245.00sqm	Struck cement pointing in 1:2 with cement and fine sand mortor with all complete.	66.00/Sqm
4	105.00cum	R.C.C. Slob work in 1:2:4 with cement course and 20mm size approved stone in including its shuttering centering etc. with all complete work.	4550.00/Cum
5	82.50qtl	M.S. or iron work for rietorormante in slob work including its cutting bending & binding with all complete.	4250.00/Qtl
6	10580 Nos 5.00cum	Deduction of old materiel. A. Brick B. Brick Ballast.	3500% 350.00/Cum

I/We are registered as.....class contractor for the authroised to road/building/sewer/electrical work/water mains and supply of materials for the current year and are authorized to tender for this work as per regd.

I/We have deposited earnest money as detailed given belwo:

N.S.C.C.D.R.F.D.R No:

Dated

O I/We hereby agreed to execute the above work at in fig.....%(percentage) above/below the above estimate rate based on prevalent schedule of rate.

Contractor

T/2
Schedule of Tender
P.W.D.Nagar Nigam Allahabad

Estimated Cost Rs. 9,91,600/--

Tender due on: 07-09-2011

Earnest money Rs: 99,160/--

Tender cost Rs 500/-

Name of work : वार्ड- 12 मलाकराज मुख्य मार्ग पर नाली निर्माण तथा कवरिंग कार्य भाग-1।

Name of Contractor

J.E.

A.E.

S.No:	Quantity	Particulars	Rate/per
1	84.00cum	Dismantling of R.C.C./R B Slob including supply of labour T&P with all complete.	210.00/Cum
2	59.00cum	Dismantling of Brick Work with all complete the work.	92.00/Cum
3	168.00cum	Earth work in excavation in found with foul position lead upto 30 m and lift upto 1.5 m with all complete work.	60.00/Cum
4	23.00cum	Cement concrete in 1:6:12 with cement fine sand and 40 m gauge brick ballast with all complete work.	1600.00/Cum
5	160.00cum	M-150 brick work in 1:6 cement and sand mortar in foundation with all labour T&P complete work.	2100.00 /Cum
6	643.00sqm	Struck cement pointing in 1:2 cement and sand mortar with all labour T&P complete.	66.00/Sqm
7	124.00sqm	Flush Pointing in 1:2 with cement and fine sand mortar with all complete.	50.00/Sqm
8	68.20cum	R.C.C. Slob work in 1:2:4 with cement course and 20mm size approved stone in including its shuttering centering etc. with all complete work.	4550.00/Cum
9	53.60qtl	M.S. or iron work for rietormante in slob work including its cutting bending & binding with all complete.	4250.00/Qtl
10	1 Job	Diversion of sludge dirty water with all complete work.	2000/Job
11	2.00 Nos	Making Banding with empty cement bag, full of local sand including molding sticking etc. with all complete work.	991.00/Each
12	2 days	Charges for dewatering of sludge dirty water by dewatering pump including & operate with all complete work.	800.00/Days
13	219.00cum	Cortege/Disposal of earth upto 5 Kmt distance form the site including loading & unloading with all complete work.	103.90/Cum
14	6808 Nos 44.20cum	Deduction of old materiel. C. Brick D. Brick Ballast.	3500% 350.00/Cum

I/We are registered as.....class contractor for the authroised to road/building/sewer/electrical work/water mains and supply of materials for the current year and are authorized to tender for this work as per regd.

I/We have deposited earnest money as detailed given below:

N.S.C.C.D.R.F.D.R No:

Dated

O I/We hereby agreed to execute the above work at in fig.....%(percentage) above/below the above estimate rate based on prevalent schedule of rate.

Contractor

T/3
Schedule of Tender
P.W.D.Nagar Nigam Allahabad

Estimated Cost Rs. 4, 71,400/--

Tender due on: 07-09-2011

Earnest money Rs: 47,140/--

Tender cost Rs 300/-

Name of work: मलिन बस्ती खारिया की बाहरी नाली नेहरू पार्क रोड के किनारे का सुधार कार्य।

Name of Contractor

J.E.

A.E.

S.No:	Quantity	Particulars	Rate/per
1	23.00cum	Dismantling of earth brick work including all complete	92.00/Cum
2	67.50cum	Earth work in excavation in ordinary soil including all complete.	68.00/Cum
3	18.00cum	Cement concrete in 1:6:12 cement sand and brick ballast including all complete.	1885.00/Cum
4	67.25cum	M-150 brick work in 1:4 with cement and fine sand mortar with all complete.	2930.00 /Cum
5	175.00sqm	Struck cement pointing in 1:2 with cement and fine sand mortar with all complete.	93.00/Sqm
6	22.80cum	R.C.C. Slob work in 1:2:4 with cement course sand and 3/m stone grit all complete work.	5990.00/Cum
7	180.00qtl	Mild stone in R.C.C. slob including all complete work.	4870.00/Qtl
8	47.25cum	Cortege/Disposal of earth upto 3Kmt distance from the site including loading & unloading with all complete work.	83.40/Cum
9	2500 Nos 19.00cum	Deduction of old materiel. E. Brick F. Brick Ballast.	3500% 350.00/Cum

I/We are registered as.....class contractor for the authroised to road/building/sewer/electrical work/water mains and supply of materials for the current year and are authorized to tender for this work as per regd.

I/We have deposited earnest money as detailed given belwo:

N.S.C.C.D.R.F.D.R No:

Dated

O I/We hereby agreed to execute the above work at in fig.....%(percentage) above/below the above estimate rate based on prevalent schedule of rate.

Contractor

T/4
Schedule of Tender
P.W.D.Nagar Nigam Allahabad

Estimated Cost Rs. 9, 46,300/--

Tender due on: 07-09-20110

Earnest money Rs: 94,630/--

Tender cost Rs 500/-

Name of work: जैरामपुर पटपर मलिन बस्ती में श्री पी०एम० मिश्रा के मकान से शिवम् स्वीट तक नाली सुधार कार्य।

Name of Contractor

J.E.	Quantity	Particulars	A.E.
S.No:	Quantity	Particulars	Rate/per
1	38.00cum	Dismantling of earth brick work including all complete	92.00/Cum
2	286.00cum	Earth work in excavation in ordinary soil including all complete.	68.00/Cum
3	26.20cum	Cement concrete in 1:6:12 cement sand and brick ballast including all complete.	1885.00/Cum
4	142.00cum	M-150 brick work in 1:4 with cement and fine sand mortor with all complete.	2930.00 /Cum
5	509.00sqm	Struck cement pointing in 1:2 with cement and fine sand mortor with all complete.	93.00/Sqm
6	37.20cum	R.C.C. Slob work in 1:2:4 with cement course sand and 3/m stone grit all complete work.	5990.00/Cum
7	29.20qtl	Mild stone in R.C.C. slob including all complete work.	4870.00/Qtl
8	50 day	Dismantling of drainage water with diesel pumping machine including ballast.	800/Days
9	1 Job	Providing barricading on both soil of drain including all complete.	4000/ Job
10	200.00cum	Cortege/Disposal of earth upto 3Kmt distance from the site including loading & unloading with all complete work.	83.40/Cum
11	4000 Nos 30.00cum	Deduction of old materiel. G. Brick H. Brick Ballast.	3500% 350.00/Cum

I/We are registered as.....class contractor for the authroised to road/building/sewer/electrical work/water mains and supply of materials for the current year and are authorized to tender for this work as per regd.

I/We have deposited earnest money as detailed given belwo:

N.S.C.C.D.R.F.D.R No:

Dated

O I/We hereby agreed to execute the above work at in fig.....%(percentage) above/below the above estimate rate based on prevalent schedule of rate.

Contractor

T/5
Schedule of Tender
P.W.D.Nagar Nigam Allahabad

Estimated Cost Rs. 8, 55,300/--

Tender due on: 07-09-2011

Earnest money Rs: 85,530/--

Tender cost Rs 500/-

Name of work: जैरामपुर पटपर मलिन बस्ती में बाहरी नाली शिवम् स्वीट से प्रजापति मार्केट तक नाली सुधार कार्य।

Name of Contractor

J.E.	Quantity	Particulars	A.E.
S.No:	Quantity	Particulars	Rate/per
1	31.00cum	Dismantling of earth brick work including all complete	92.00/Cum
2	295.00cum	Earth work in excavation in ordinary soil including all complete.	68.00/Cum
3	28.00cum	Cement concrete in 1:6:12 cement sand and brick ballast including all complete.	1885.00/Cum
4	147.00cum	M-150 brick work in 1:4 with cement and fine sand mortor with all complete.	2930.00 /Cum
5	424.00sqm	Struck cement pointing in 1:2 with cement and fine sand mortor with all complete.	93.00/Sqm
6	28.00cum	R.C.C. Slob work in 1:2:4 with cement course sand and 3/m stone grit all complete work.	5990.00/Cum
7	22.00qtl	Mild stone in R.C.C. slob including all complete work.	4870.00/Qtl
8	40 day	Dismantling of drainage water with diesel pumping machine including ballast.	800/Days
9	1 Job	Providing barricading on both soil of drain including all complete.	4000/ Job
10	207.00cum	Cortege/Disposal of earth upto 3Kmt distance from the site including loading & unloading with all complete work.	83.40/Cum
11	3000 Nos 25.00cum	Deduction of old materiel. I. Brick J. Brick Ballast.	3500% 350.00/Cum

I/We are registered as.....class contractor for the authroised to road/building/sewer/electrical work/water mains and supply of materials for the current year and are authorized to tender for this work as per regd.

I/We have deposed earnest money as detailed given belwo:

N.S.C.C.D.R.F.D.R No:

Dated

O I/We hereby agreed to execute the above work at in fig.....%(percentage) above/below the above estimate rate based on prevalent schedule of rate.

Contractor

T/6
Schedule of Tender
P.W.D.Nagar Nigam Allahabad

Estimated Cost Rs. 9,99,520/--

Tender due on: 07-09-2011

Earnest money Rs: 99,952/--

Tender cost Rs 500/-

Name of work : वार्ड- 12 मलाकराज में रेलवे लाईन के किनारे नाला निर्माण एवं कवरिंग कार्य भाग-2।

Name of Contractor

J.E.

A.E.

S.No:	Quantity	Particulars	Rate/per
1	14.00cum	Dismantling of Brick Work with all complete the work.	92.00/Cum
2	603.00cum	Earth work in excavation in foundndation foul position lead upto 30 m and lift upto 1.5 m with all complete work.	60.00/Cum
3	71.00cum	Cement concrete in 1:6:12 with cement fine sand and 40 m gauge brick ballast with all complete work.	1600.00/Cum
4	263.00cum	M-150 brick work in 1:6 with cement and fine sand mortor with all complete.	2100.00 /Cum
5	683.00sqm	Struck cement pointing in 1:2 with cement and fine sand mortor with all complete.	66.00/Sqm
6	203.00sqm	Flush Pointing in 1:2 with cement and fine sand mortor with all complete.	50.00/Sqm
7	22.00cum	R.C.C. Slob work in 1:2:4 with cement course and 20mm size approved stone in including its shuttering centering etc. with all complete work.	4550.00/Cum
8	17.20qtl	M.S. or iron work for rietorormante in slob work including its cutting bending & binding with all complete.	4250.00/Qtl
9	1 Job	Diversion of sludge dirty water with all complete work.	3000/Job
10	6.00 Nos	Making Banding with empty cement bag, full of local sand including molding sticking etc. with all complete work.	991.00/Each
11	10 days	Charges for dewatering of sludge dirty water by dewatering pump including & operate with all complete work.	800.00/Days
12	483.00cum	Cortege/Disposal of earth upto 5Kmt distance form the site including loading & unloading with all complete work.	103.90/Cum
13	1610 Nos 10.50cum	Deduction of old materiel. K. Brick L. Brick Ballast.	3500% 350.00/Cum

I/We are registered as.....class contractor for the authorized to road/building/sewer/electrical work/water mains and supply of materials for the current year and are authorized to tender for this work as per regd.

I/We have deposited earnest money as detailed given below:

N.S.C.C.D.R.F.D.R No:

Dated

O I/We hereby agreed to execute the above work at in fig.....%(percentage) above/below the above estimate rate based on prevalent schedule of rate.

Contractor